



PLANT SCHEDULE

| TREES | QTY | COMMON NAME | BOTANICAL NAME | CONT | CAL | SIZE |
|---------------|-----------|--------------------|-----------------------------|--------|----------------|-------------|
| | 30 | White Fringetree | Chionanthus virginicus | | 2'-2 1/2" Cal. | 10'-12" Ht. |
| | 23 | Savannah Holly | Ilex x attenuata 'Savannah' | 15 gal | 1" Cal | |
| | 9 | Shumard Red Oak | Quercus shumardii | | 2'-2.5" cal | 10'-12" Ht. |
| | 2 | Southern Live Oak | Quercus virginiana | | 2.5" Cal | 10'-12" Ht. |
| | 4 | Bald Cypress | Taxodium distichum | | 2'-2.5" cal | 10'-12" Ht. |
| | 6 | American Elm | Ulmus americana 'Princeton' | | 2'-2.5" cal | 10'-12" Ht. |
| | 20 | Allee Lacebark Elm | Ulmus parvifolia 'Allee' | | 2" Cal | 10'-12" Ht. |
| SHRUBS | QTY | COMMON NAME | BOTANICAL NAME | CONT | | SPACING |
| | 19 | Dwarf Yaupon | Ilex vomitoria 'Nana' | 3 gal | | 36" o.c. |
| GROUND COVERS | QTY | COMMON NAME | BOTANICAL NAME | CONT | | SPACING |
| | 58,839 sf | Bermuda Grass | Cynodon dactylon | sod | | |
| | 397 | Virginia Willow | Itea virginica | 3 gal | | 24" o.c. |
| | 134 sf | Stone 6" | River Stone | Rock | | |

- NOTES TO CONTRACTOR**
- Contractor shall bear the full responsibility in verifying locations of existing site utilities and shall be responsible for any damage to said utilities during construction.
 - All tree, shrub, and bed locations are to be laid out in the field by the Contractor and approved by the landscape architect prior to installation. Give landscape architect 72 hours notice.
 - Quantities are given for informational purposes only. The contractor shall be responsible for performing an independent take-off to determine quantities that meet the design intent.
 - All plant material shall be container grown unless noted otherwise.
 - Call the landscape architect at (504) 345-2639 to answer any questions.
 - Finish grade of sod panels must be flush with top of curb or edge of pavement in a straight, uniform pattern free from all debris.
 - Apply an approved pre-emergent herbicide to all bed prep areas.
 - Refer to written specifications for detailed requirements.
 - Provide protection to all finished work until accepted by owner.

THESE DRAWINGS DO NOT INCLUDE COMPONENTS FOR CONSTRUCTION SAFETY.
CALL "LOUISIANA ONE-CALL" BEFORE DIGGING
 PH. 1-(800)-272-3020

The location of existing underground utilities are shown in an approximate way only. The contractor shall determine the exact location of all existing utilities before commencing work. He agrees to be fully responsible for any and all damages which might be occasioned by his failure to exactly locate and preserve any and all underground utilities.

DANA BROWN & Associates
 DANA BROWN & ASSOCIATES, INC.
 BATON ROUGE NEW ORLEANS
 225.381.3139 504.345.2639
 www.danabrownassociates.com