# **Desmare Playground**



#### **Desmare Playground**

The residents of the Faubourg St. John are always thinking of the neighborhood's open spaces. From the Bayou, to the bridges, to the beautiful small parks, the residents proudly take a proactive response to ownership and maintenance of these spaces. The neighborhood residents want to be responsive to the needs of the growing population of young families by providing them with more opportunities that will serve the newest generation of neighborhood children.

Henry Desmare Playground, located within the 3400 block of Esplanade Avenue, is a playground in a beautiful location between an allee of Live Oaks along Esplanade Avenue and the Bayou St. John. The goal of the Faubourg St. John Neighborhood Association (FSJNA) is to revamp the currently worn down playground space to make it more welcoming for children. In 2013, the FSJNA teamed up with the local the landscape architecture firm, Dana Brown & Associates, to create a Master Plan for Desmare Playground.

**Neighborhood residents expressed interest in updating the Playground by adding the following elements:** 

- New swing set
- · New playground equipment
- Re-purposing the basketball court to be more kid friendly
- Adding exercise equipment
- Making space for kid centered neighborhood events, such as movie nights and baby play groups

FSJNA and DBA held a design charette where neighborhood residents, both adults and children, were invited to come and express what they would like to see in the Playground's Master Plan. The event was a success with a number of families showing up and showcasing their creativity. The kids painted on boxes and drew what features they would like to see in the Playground on the basketball court in chalk. The ideas ranged from jungle gyms to duck ponds, with an overwhelming response to the idea of a new swing set.

DBA developed a Master Plan to include the following elements based on the input at the charrette: provide the maximum amount of play space, increase the canopy for shade, improve circulation, separate age groups and their play equipment, provide more seating for parents, and make all amenities in the Playground ADA accessible. DBA proposed to solve the Playground's standing water issue by regrading the site and installing a rain garden. DBA also separated the Master Plan into phases so that sections of the plan can be implemented as FSJNA raises funds.


Fund raising is ongoing. To date the FSJNA has raised more than \$34,000 and paid for the Master Plan design work completed by DBA. FSJNA now has the funds for the first phase of work, thanks to NORDC covering the cost for the swing set safety surface.

# **Desmare Playground**



Existing entry gate

#### **Desmare Playground:** Neighborhood Analysis



# **Desmare Playground: Existing Conditions**



Existing central play area



Existing entry into the playground



**Existing seating** 



Existing court with play equipment

## **Desmare Playground:** Design Charette









#### **Desmare Playground:** Master Plan



## **Desmare Playground:** Master Plan



# **Desmare Playground:** Master Plan



## **Desmare Playground:** Play Equipment



2 to 5 year old play area



2 to 5 year old play area






5 to 12 year old play area

#### **COLOR OPTIONS:**





#### **Desmare Playground: Phases**




## **Desmare Playground: Phase 1**



## **Desmare Playground: Phase 1 OPC**

Concrete Walks	QTY.	UNIT	COST	TOTAL	NOTES
New Entry Walk; 4" thick	175	SF	\$ 4	\$ 700	
Bike Rack base; 4" thick	100	SF	\$ 4	\$ 400	
	\$			1,100	
Rain Garden	QTY.	UNIT	COST	TOTAL	
Grading and Excavation	107	CY	\$ 30	\$ 3,200	
Bioswale Soil	100	CY	\$ 20	\$ 2,000	
Plants; 1 gal at 18" O.C.	125	EA	\$ 15	\$ 1,875	Copper Iris, White Muhly, Yellow Canas
	\$			7,075	
Fence Improvements	QTY.	UNIT	COST	TOTAL	
Entry Gate; 5' chain link with latch	1	EA	\$ 600	\$ 600	
Fig Vine; 4" cont. at 36" O.C.	30	EA	\$ 15	\$ 450	
	\$			1,050	
Site Furniture	QTY.	UNIT	COST	TOTAL	
Phase 1 Progress Signage	1	LS	\$ 600	\$ 600	local artist award design and install
Bike Racks; Landscape Forms Loop	3	EA	\$ 450	\$ 1,350	
Trash Can; Landscape Forms Scarborough	1	EA	\$ 1,300	\$ 1,300	
	\$			2,650	
Equipment	QTY.	UNIT	COST	TOTAL	
Swings	1	EA	\$ 8,079	\$ 8,079	includes delivery and install
Swings concrete pad; 4" thick	1,925	SF	\$ 4	\$ 7,700	
Swing Safety Surface	1	LS	\$ 25,145	\$ -	includes delivery and install; tax free for NORDO
				15,779	
Landscape Improvements	QTY.	UNIT	COST	TOTAL	
Bosque: Bald Cypress, 30 gal.	13	EA	\$ 200	\$ 2,600	install and guaranteed for 1 year
Bosque: Pervious Concrete Path	105	SF	\$ 7	\$ 735	
Bosque: Concrete Curb	90	LF	\$ 20	\$ 1,800	
Bosque: Ground Material, pine mulch	86	SY	\$ 5	\$ 431	
Trees; 30 gal.	13	EA	\$ 200	\$ 2,600	Swamp Red Maple, Pond Cypress, Green Ash
Hydroseeding	4,625	SF	\$ 0.30	\$ 1,388	
Volunteer Planting: materials and supplies	1	LS	\$ 1,000	\$ 1,000	
				10,553	
	SUB-TOTAL			\$ 38,207	1
	CONTINGENCY		10%	\$ 3,821	
	CONTRACTOR		15%	\$ 6,304	
	DESIGNER FEE		12%	\$ 5,800	
PRELI	MINARY WORK			\$ 2,500	
	TOTAL			\$ 56,632	

## **Desmare Playground:** Sustainable Water Management



DESMARE PLAYGROUND					
		Proposed			
	Proposed	Runoff			
	Runoff (cf)	(Acre/ft)			
1 Year Storm	1,258	0.03			
2 Year Storm	1,794	0.04			
10 Year Storm	2,883	0.07			

Rain Garde Size	en	Above (		Below Ground Capacity		
Sq. Ft.		Average Depth (ft.)	Capacity (cf)	Soil Depth (ft.)	Capacity (cf)	
960		0.5	480	1	288	

Captured				
% Captured				
61%				
43%				
27%				

#### **Desmare Playground: Plant Material**



#### **Desmare Playground:** Fund Raising Signage & Site Furniture





**Location for Master Planning signage** 







**Site Furniture:** stainless steel furniture from Landscape Forms